



City of Franklin

5550 W. Airways Avenue, Franklin, WI 53132

Phone: (414) 421-2581/ (414) 421-2613

Fax: (414) 421-1143

PRECONSTRUCTION REMINDERS

1. Meeting with utility personnel, job foreman, & inspector before construction on jobsite
2. Main construction will be free standing
3. 1 ¼" full bore curb stop – all compression fittings, no flare fittings
4. Double bagging of all metal
5. All bolts to be core ten blue
6. Tracer wire to be brought up behind hydrants into capped, 2" PVC pipe
7. SDR-14 to be used for hydrant leads
8. Plastic sheeting used over 1" clear stone around hydrant installation
9. Utility personnel will be present during pressure tests and connections. All valves operated by utility personnel only.
10. Samples will be taken on all dead ends of system construction.
11. Until further notice, we are not requiring ductile valve bodies.
12. Contractors to provide notice to employees in accordance of OSHA standards.
13. Calculate total gallonage of new water main time 3, to calculate total amount of charges to contractor for flushing costs.